

1 080062

4-13-90

153

R

API NUMBER 15- 071-20,503-0000

SW SW NW, SEC. 25, T 18 S, R 43 W/E

2970 feet from S section line

4950 feet from E section line

Lease Name Johnson-Moore Well # 1-25

County Greeley 171.02

Well Total Depth 5262 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 618

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Operator: Murfin Drilling Company
Name & Address 250 North Water, Suite 300
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 13 Month: 4 Year: 19 90

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2549'

1st plug at 2550' with 50 sx cement, 2nd plug at 1275' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 p.m. Day: 13 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2550' with 50 sx cement,

2nd plug at 1275' with 80 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used Pozmix 6% gel by B.J. Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED 4-23-90

DATE 5-4-90 CONSERVATION DIVISION Wichita, Kansas

INV. NO. 28015

Signed Mike Spain (TECHNICIAN)