

To: 1 071026 2-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,557 -0000 149  
NE SE NW, SEC. 25, T 18 S, R 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8458

Operator: Trans-Western Petroleum, Inc.  
Name & Address P.O. Box 276  
Golden, CO 80402

1500 feet from N ~~XX~~ section line  
2310 feet from W ~~XX~~ section line

Lease Name Moore-Johnson Well # 1  
County Greeley 170.62

Well Total Depth 5250 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 625

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 19 Month: 2 Year: 19 92

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2542-72'  
1st plug at 2572' with 50 sx cement, 2nd plug at 1650' with 80 sx cement,  
3rd plug at 825' with 30 sx cement, 4th plug at 640' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 p.m. Day: 19 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2572' with 50 sx cement,

2nd plug at 1650' with 80 sx cement, 3rd plug at 825' with 30 sx cement,

4th plug at 640' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1992  
2-26-92  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floeal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(XXXXXX) observe this plugging.

DATE 3-16-92

Signed Dan Johnson  
(TECHNICIAN)

INV. NO. 34755  
2-19 MAY 19 1992