

To: 1 051492
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-2
API NUMBER 15- 071-20,551-0000 81
W/2 W/2 SE, SEC. 25, T. 18 S, R. 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606
Operator: Murfin Drilling Company, Inc.
Name & Address 250 N. Water, Suite 300
Wichita, KS 67202

1320 feet from S section line
2310 feet from E section line
Lease Name Schmidt Well # B-2
County Greeley 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 606

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 2 Month: 11 Year: 19 91

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2510-40'
1st plug at 2540' with 50 sx cement, 2nd plug at 1600' with 80 sx cement,
3rd plug at 630' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 a.m. Day: 2 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2540' with 50 sx cement,
2nd plug at 1600' with 80 sx cement,
3rd plug at 630' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1991
11-6-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

1 (XXX) did not observe this plugging.

DATE 6-12-6-91
INV. NO. 34015

Signed Richard W. Lacey
(TECHNICIAN)