



15-051-23113-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

AUG 24 1982  
08-24-1982  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Stan Lingreen of Reelin Ind. Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: Engel Oil Co.

Complete Address: P.O. Box 295, Victoria, Ks. 67671

Lease Name: Hertel Bros. Well No. 1

Location: SW SE NE Sec. 22 Twp. 14 Rge. 17 (E) (W)

County: Ellis Total Depth: 3600'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Lingreen was instructed to plug the well as follows:

8 5/8" - 272' SP. cas. w/175 sacks common - 2% Rel. - 3% Cal. Cl.  
Ordered 140 sacks 50 permix - 4% Rel. - 3% Cal. Cl. + 8 5/8" plugs. Spot w/ drill stem  
w/ heavy mud between all plugs. 1st plug C 700' w/ 80 sacks.  
2nd plug C 97' w/ 40 sacks.  
3rd plug - solid bridge of hulls & plug C 40' w/ 10 sacks.  
Circulate 10 sacks in rat hole.

Very truly yours,

Conservation Division Agent

OIC