

State of Kansas



15-051-21309-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 04 1977
04-04-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. ~~XXXX~~ Robey of Icer Addis has this

date requested permission to plug the following described well:

Mr. ~~XXXX~~ Robey guarantees payment of the plugging fee.

Operator's full Name: Icer Addis

Complete Address: Box 8038, Wichita, Ks.

Lease Name: Hertel Well No. 1

Location: NE NW NE Sec. 22 Twp. 14 Rge. (E)(W) 17

County: Ellis Total Depth 3580' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Robey was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Conservation Division Agent