

State of Kansas



15-051-20511-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 29 1969

CONSERVATION DIVISION
 Wichita, Kansas

10-29-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B - B Drlg. has this
 date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Co.

Complete Address: 1130 Wichita Plaza Wichita, Ks.

Lease Name: Yunker Well No. 2

Location: SW NW NW Sec. 22 Twp. 14 Rge. 17 (E)(W) XX

County: Ellis Total Depth 3567' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

70 sk cmt thru drill pipe. Heavy mud to 160' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base od cellar.

Very truly yours,

Leo F. Massey
 Conservation Division Agent