



15-051-22006-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Melvin Helms of Helms Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Helms Casing Pulling

Complete Address: Box 176 Chase, Kans. 67526

Lease Name: Gabel Well No. #1

Location: ~~C-4-NE-NE~~ ^{NESENE} AND ^{EA} Sec. 19 Twp. 14 Rge. 17 (E) (W)

County: ELLIS Total Depth: 3560

Abandoned Oil Well Gas Well Input Well SWD Well

Other well as hereafter indicated: _____

FEB 24 1981
DCA
02-24-1981
CONSERVATION DIVISION
Wichita, Kansas

Mr. Helms was instructed to plug the well as follows:

8 5/8" 225 ^{FE} / 125 ST CNT. → 5 1/2" SET @ 3560 ^{FE} / 100 ST CNT.
PERF'S TOP 3413 ^{FE} PLUG BACK - 3500 ^{FE} SAND BOTTOM TO 3363 1/5 ST CNT.
SHOT PIPE TWICE, RECOVERED 2826 ^{FE}
ORDERED - 140 ST 50/50 Pozmix 4% Gel - 3% CH-CL - 19 ST GEL. → 5 HULL'S + 8 5/8" PLUG.
PUMPED IN 8 5/8" WITH PUMP TRUCK. - 4 ST HULL'S - 15 ST GEL. → 60 ST CNT.
2 ST GEL - RELEASED PLUG AND 80 ST CNT. MAX PRESSURE - 900 ^{PSI} TO 450 ^{PSI}

Very truly yours, (By allied)

Marion Schmidt
Conservation Division Agent