



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Flake of Woodman-Tarnitti has this  
date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum, Inc.

Complete Address: 445 Olive W. Garvey Bldg., Wichita, Ks.

Lease Name: Pfannenstiel Well No. 1

Location: SW NW NW Sec. 35 Twp. 14 Rge. (E)(W) 18

County: Ellis Total Depth 3665 Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Flake was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug. 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent