

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 25 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: 217 N. Water Wichita, ^As.

Lease Name: Mary Engle Well No. 2-D

Location: SE SW SW Sec. 27 Twp. 14 Rge. (E)(W) 18

County: Ellis Total Depth 3677' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]
 Conservation Division Agent