

State of Kansas



15-051-20009-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1967
02-01-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lattimer of Raymond Oil Co. Inc., has this
date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company Inc.,

Complete Address: 410 4th Nat'l Bank Bldg. Wichita, Kansas

Lease Name: Pfeifer Well No. 1

Location: SW NE NE Sec. 27 Twp. 14 Rge. 18 (E)(W) X

County Ellis Total Depth 2890' Oil Well

Gas Well Input Well SWD Well D & AX Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

Gun-pits, circulate heavy mud, set cementing plug at 500' and displace
25 sc cement thru drill pipe. Heavy mud to 260' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Leo F. Messing
Conservation Division Agent