

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 -22,845-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name N.B. Co., Inc.

Complete Address P.O. Box 506 S. Kansas, Russell, Ks. 67665

Lease Name Boone Well No. 1

Location NE NW SE Sec. 30 Twp. 14 Rge. 17 (East) (West)

County Ellis Total Depth 3512'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations

Address P.O. Box 506, Russell, Ks. 67665 License No. \_\_\_\_\_

Operation Completed: Hour: 2:15 AM Day: 3 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-729' S.P. cuc. w/350 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 850' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 729' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

**INVOICED**

DATE 4-6-82  
INV. NO. 9857-W

Signed: \_\_\_\_\_  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
APR - 5 1982  
04-05-1982  
CONSERVATION DIVISION  
Wichita Kan.