

15-051-01030-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW NW SW

SEC. 27 TWP. 14 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Catherine

Operator Lion Oil Co Address Box 552 Pratt, Kans

Field _____ County Ellis

Total Depth 3497 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 253' circulated with cement - 5 1/2" at 3497' with 150
sax cement behind - D-V tool at 1173', circulated with 600 sax
cement from 1173' - Lane Wells plugs at 3375' - top perforations
3270'.

Pumped hole full Halcogel, followed by 40 sax cement - cementing
plug pumped to 325' - cement from 325' to 0'.

No pipe recovery - Mudding and cementing by Halliburton Co -
pump pressure during mudding and cementing 2000#.

PLUGGING
FILE SEC 27 T 14 R 17W
BOOK PAGE 86 LINE 20

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1953
03-23-1953
CONSERVATION DIVISION
Wichita, Kansas

Edward J. Pett
District Conservation Agent
Date 3-20-53