

15-051-06805-00-00

VR

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW SW SW

SEC. 27 TWP. 14 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Jerome

Operator Lion Oil Co Address Pratt, Kans

Field _____ County Ellis

Total Depth 3498 Feet.

Plugging Contractor Halliburton Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 207' circulated with cement. 5 1/2" at 3478' with

150 sax cement behind - DV tool set at 1175' - 5 1/2" circulated

with 600 sax cement 1175' to 0'.

Pumped 5 1/2" full commercial mud (35 sax) pumped cementing plug

to 325' followed by ~~sax~~ 40 sax cement, filling hole with

cement 325' to 0'.

Mudding and cementing by Halliburton Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1954
0503-1954
CONSERVATION DIVISION
Wichita, Kansas

E. J. Perry
District Conservation Agent

Date 4-30-54

PLUGGING
FILE SEC. 27 14 R 17W
BOOK PAGE 27 LINE 9