

NOTE LOG

15071-20453-0000

WELL Rebecca K. Bounds No. 2
RIG Longyear 603
ORIGIN: RIG CDF OTHER
AUTHOR R. P. Lawrence

DATE: 27Apr88 TIME 09:12

TYPE OF LOG ENTRY:
DECISION
 NOTE
 RECOMMENDATION

NUMBER OF ATTACHMENTS _____
PERSON SUBMITTING NOTE LOG (Initials) RPL

- BITS/BHA/DIR LOGGING COST TROUBLE COMPLETION
- MUDS/SOLIDS CAGING BOP/WELL C. P & A COMMUNICATIONS
- GENERAL WELL CEMENTING TESTING LOGISTICS _____

OTHER

Plug and Abandonment detail for Rebecca K. Bounds No. 2

1. Set plug #1 from 1483' to 1040' with 28 sks of 60/40 Pozmix + 6% gel. Preceded cement with 8 bbls of water and displaced with 9.9 bbls of water.
2. POH and LD 101 Drill Rod to 100'.
3. Circulate for 10 minutes.
4. Set plug #2 from 700' to surface. Pumped 1/2 sks of 60/40 Pozmix + 6% gel. Pumped 5 bbls of water ahead of cement.
5. POH and LD Drill Rods.
6. Set 10 sks top plug with 60/40 Pozmix + 6% gel.
7. Well plugged at 2230 hours on April 25, 1988.

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1988
5-13-88

CONSERVATION DIVISION
Wichita, Kansas

DATE 27Apr88 DEPTH 0 WELL Rebecca K. Bounds No. 1A DAYS 23

NOTE LOG