

15-053-20113-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Bell & Rupe

Complete Address 222 Brown Bldg., Wichita, Kansas 67202

Lease Name Vopat "C" Well No. 1

Location C W/2 NE SW Sec. 23 Twp. 14 Rge. 10 (E) (W) X

County Ellsworth Total Depth 3275'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor American Drilling Corp., Ltd.

Address 550 Sutton Place, Wichita, Kansas License No.       

Operation Completed: Hour 10:30 AM Day 28 Month December Year 1969

The above well was plugged as follows:

Hole filled with mud to 265'. Plug and 1/4 sack hulls pushed to 265' and hole cemented  
with 25 sacks cement through drill pipe. Hole filled with mud to 40'. Plug and 1/2  
sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.  
Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed:   
Well Plugging Supervisor

INVOICED  
DATE 12/31/69  
INV. NO. 1179-W