

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1974
01-10-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. G. Stephenson
Complete Address 360 Farm Credit Bank Bldg., Wichita, Kansas
Lease Name Kepka Well No. 1
Location NE NE NE Sec. 28 Twp. 14 Rge. 10 (E) (W) X
County Ellsworth Total Depth 1204'
Original TD 2910'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated OWNO (Unable to drill obstruction in hole.)

Plugging Contractor Wilson Exploration and Development and Sun Cementing Co.

Address P.O. Box 338, Wilson, Kansas License No.

Operation Completed: Hour 6 PM Day 7 Month January Year 1974

The above well was plugged as follows:

Hole filled with mud. Plug pushed to 500' and hole cemented with 40 sacks cement.

25 sacks cement pumped through drill pipe at 250'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.

Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. L...*
Well Plugging Supervisor

INVOICED

DATE 1/10/74

INV. NO. 8397-W