

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
OCT 07 1982

FORM CP-3
Rev. 1-8-82

API Number 15-051-06786.00.00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Sun Exploration & Production

Complete Address 4500 S. Garnett, P.O. Box 35567, Tulsa, Ok. 74135

Lease Name Dreiling Well No. C-1

Location SW SW SW Sec. 35 Twp. 13 Rge. 20 (East) (West)

County Ellis Total Depth 3839'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Melso Casing Pulling

Address Box 176, Chase, Ks, 67524 License No. _____

Operation Completed: Hour: 11:50 AM Day: 30 Month: 10 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 1531' SP. cas. w/ 440 sacks cement. 5 1/2" set at 3832' w/ 150 sacks cement.
Top perf. 3423'. Plugged bottom w/ sand + 5 sacks cement to 1800'. Junk in hole
to 1900'. Shot pipe 1 time + recovered 1785'. Ordered 140 sacks ⁵⁰ permix - 4 7/8" Gel.
3% Col. ll., 20 sacks Gel, 5 sacks hulla + 8 5/8" plug. Pumped in 8 5/8", 4 sacks hulla,
15 sacks Gel, 70 sacks cement, 5 sacks Gel, 1 sack hulla; released plug + followed
w/ 70 sacks cement.

Maximum pressure 250 pounds.

Amount of Surface Casing: 1531' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Rette R. Schel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED
DATE 10-14-82
INV. NO. 1255-U

Signed: _____
Conservation Division Agent