

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben Drlg. Inc. 15-051-06788-00-00
Complete Address P. O. Box 486 Great Bend, Kansas 67530
Lease Name Dreiling Well No. 1
Location SW NW SW Sec. 35 Twp. 13 Rge. (E) (W) 20
County Ellis Total Depth 3846
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Co. Inc.
Address Box 221 Great Bend, Kansas License No. 637
Operation Completed: Hour 11 A Day 7 Month 8 Year 1970

The above well was plugged as follows:

Total Depth 3846 10 3/4 csg set at 1540' cwc

5 1/2 csg set at 3838' cw 150 sk cmt

5 1/2 csg perf. (3524-3546)

Filled 5 1/2 csg W/sd (3825-3846) Dumped 1/2 sk cmt W/dump bailer. (3800-3825)

Set wood plug at 3250 poured 10' sd and dumped 5 sk cmt W/dump bailer. (3200-3250)

Mud Recov. 800' of 5 1/2 csg.

Mud to 600' - rock & sand (590-600) readymix cmt (340-590) Mud to 150' ~~readymix~~

~~cmt (0-150)~~ rock & sand (150-160) readymix cmt (0-150)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Messing
Well Plugging Supervisor

INVOICED

DATE 8/10/70

INV. NO. 2360-u