

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 18 1977  
2-18-77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 051 - 21,262 - 00-00 (of this well)

Operator's Full Name Bill Witcraft  
Complete Address Box 811, Great Bend, Kansas 67530  
Lease Name Storm Well No. 1  
Location NW NW NW Sec. 35 Twp. 13 Rge. (E) (W) 20  
County Ellis Total Depth 3866'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Duke Drlg.  
Address Great Bend, Kansas License No.         
Operation Completed: Hour 4:30 A Day 17 Month 2 Year 1977

The above well was plugged as follows:

RTD 3866' 8 5/8 csg set 205' cwc 150 sx. Flg. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.  
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2-18-77

INV. NO. 4655-w