

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alco Oil & Gas Corp.¹ 15:051-04440-00-02
Complete Address: P. O. Box 52027, Lafayette, Louisiana 70501
~~Box 520 - Great Bend, Kansas~~

Lease Name Engel SWD Well No. A-1

Location NW NW NW Sec. 36 Twp. 13 Rge. 20 (E) (W) X

County Ellis Total Depth 3960

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5 P Day 4 Month 6 Year 1968

The Above well was plugged as follows:

Total Depth 3960' 10 3/4' csg set at 195' cwc.

5 1/2' csg set at 3870' cw 100 sc cement.

5 1/2' stage collar set at 1505' cwc 550 sc.

No Pipe recov.

Pumped thru 5 1/2' plg container with 40 sc gel W/5 sc hulls 4' Plug and 100 sc 50-50 poz cement. Pumping pres. 790-1400. SI pres. 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 6/10/68
INV. NO. 7914-W