

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1974
6-13-74

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Ladd Petroleum Corp. 15-051-00938-00-00

Complete Address Box 520 Great Bend, Kansas 67530

Lease Name Engle "E" Well No. 1

Location NW NE SE Sec. 36 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3880'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn Casing Pulling

Address Box 156 Ellinwood, Kansas License No. 686

Operation Completed: Hour 12:30 P Day 12 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3880' 8 5/8 csg set at 212' cwc

5 1/2 csg set at 3876' cw 100 sk cmt.

5 1/2 csg squeezed at 780-795 with 300 sx cem. & circ. to surface. No pipe recovered.

Pumped down 5 1/2 csg with 25 sk cmt (3880-3580) -25 sk gel & water W/400 lbs hulls

(3580-600) released 5 1/2 plug & pumped 50 sk cmt. (600' base of cellar) 750 lbs PP.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 6/21/74
INV. NO. 9353-W