

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1974
5-6-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name G. N. Rupe 15-051-19103-00-01
Complete Address 925 O. W. Garvey Bldg., Wichita, Kansas 67202
Lease Name Engel (SWD) Well No. 2
Location S/2 S/2 NW NW Sec. 36 Twp. 13 Rge. (E) (W) 20
County Ellis Total Depth 3846'
Abandoned Oil Well Gas Well Input Well SWD Well XX D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by Sun Cementing Co.
Address Hays, Kansas 67601 License No.
Operation Completed: Hour 11:30 A Day 2 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3846' 8 5/8 csg set at 205' cwc 150 sk.
4 1/2 csg set at 3842' cw 150 sk.
2-stage collar set at 1520' circ to surface with 450 sk cmt. No pipe recovered.
Pumped down 4 1/2 csg with 30 sk gel & water --released plug and pumped 80 sk cement
6% gel W/100 lbs hulls. PP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/8/74
INV. NO. 9050-W

Signed: Leo Z. Massey
Well Plugging Supervisor