

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC 10 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051 -21,251 -0000 (of this well)

Operator's Full Name Kansas Petroleum, Inc.

Complete Address 500 Insurance Bldg., Wichita, Kansas

Lease Name Engel Well No. 1

Location NE NW SE Sec. 36 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3875'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No. _____

Operation Completed: Hour 1:30 P Day 7 Month 12 Year 1976

The above well was plugged as follows:

RTD 3875' 8 5/8 csg set 256' cwc 160 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-10-76

INV. NO. 4296-W