

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1976
1-9-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name G. N. Rupe 15-051-21132-00-00

Complete Address 200 W. Douglas, Suite 925, Wichita, Kansas

Lease Name Engel Well No. 2

Location NW SW NW Sec. 36 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3862'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:30 A Day 7 Month 1 Year 1976

The above well was plugged as follows:

RTD 3862' 8 5/8 csg set 204' cwc 110 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Russ Massey
Well Plugging Supervisor

INVOICED

DATE 1-9-76

INV. NO. 2545-W