

15-051-05459-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Petroleum Company
Complete Address 2915 N. Lincoln Oklahoma City, Oklahoma 73105
Lease Name Johnson (Lizzie) "A" Well No: 33
Location SE SW NW Sec. 29 Twp. 11 Rge. (E) (W) 18
County Ellis Total Depth 3629'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Co. Tools by HOWCO
Address _____ License No. _____

Operation Completed: Hour 12 N Day 21 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3629' 10 3/4 csg set at 1240' cwc: 550'
4 1/2 csg set at 3617' cw 225 sk cmt. & perf. (3611-3617)
4 1/2 csg squeezed at 1246' W/200 sk & 1251' W/300 sk. No pipe recovered.
Ran 49 jts tbg set at 1470' -pumped 100 lbs hulls, -25 sk gel & water -displaced
20 sk cmt. Pulled 29 jts tbg set at 600' -circulated 40 sk cmt to surface. Pulled
remaining 20 jts tbg & capped 4 1/2 csg W/10 sk cmt.
Pumped 15 sk cmt down anulus with 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: L. F. Massey
Well Plugging Supervisor

INVOICED

DATE 8/25/72

INV. NO. 6223-W