

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION CNW SW

SEC. 6 TWP. 18S RGE. 39W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Brunswig

Operator Caulkins Oil Company Address c/o R. W. Rine Drilling Company
320 Central Bldg., Wichita, Kans.

Field _____ County Greeley

Total Depth 5920 Feet.

Plugging Contractor R. W. Rine Drilling Company

Plugging Contractor's License No. none required - rotary drilled dry hole

Address 320 Central Bldg., Wichita, Kansas

(Describe Briefly the manner in which the well was plugged)

504 feet of 13-3/8" surface pipe. 2596 feet of
8-5/8" intermediate string run. Filled bottom of hole
with rotary mud. Set bottom plug at 2600 feet and
30 sacks of cement. Shot off 8-5/8" at 2100 feet;
Mudded hole to 40 feet; set plug and 20 sacks of
cement filling hole with cement to base of cellar.

S. S. Greider
District Conservation Agent

Date May 23, 1956

*Rec'd
6-15-56*

PLUGGING
FILE SEC. 6 T. 18 R. 39W
BOOK PAGE 64 LINE 11