

OCT 01 1982
10-1-82
CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATIONS COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-071 - 20218-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Smith Cattle Co. Inc # 6085

Complete Address Box 399, Tribune, Kans. 67879

Lease Name Smith Cattle Co. Well No. 8

Location 640' FSL - 330' FEL Sec. 6 Twp. 18 Rge. 40 (East) (West)

County Greeley Total Depth 3040'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling service

Address Box F Sublett Kans 67877 License No. 6497

Operation Completed: Hour: 2:00 PM. Day: 25 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 3039' of 4 1/2" production pipe cemented with 300 lbs of cement. The top of perforations were at 3015'. 1st plug at bottom with 1 sbx hulls + 15 sbx cement with top at 2977'. 2nd plug at 1100' with 40 sbx of cement 3rd plug at 320' with 50 sbx of cement. 4th plug on solid bridge at 40' to 0' with 10 sbx of cement. The cement used was common cement pumped through 4 1/2" pipe as coming out of hole with hole full of heavy mud. The plugging accomplished by (over)

Amount of Surface Casing: 269' of 8 1/2" cement circulated with 200 lbs cement.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. ~~A full account for my not being present is as follows:~~

Signed: _____
Conservation Division Agent

INVOICED

DATE 1350-W

INV. NO. 10-14-82

Midwest Casing pulling services. The cement used
was common cement. They recovered ~~2350~~²³⁵⁰ of 4 1/2"
pipe.

Paul A. Luthi