

15-071-20064-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1974  
12-9-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #358, Borger, Texas.

Lease Name Byerly "A" Well No. A-1

C S E N W  
Location 1980' FNL & 1980' FWL of NW/4 Sec. 11 Twp: 18 Rge. (E) (W) 40

County Greeley Total Depth 4250'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Service Drilling Company,

Address      License No.     

Operation Completed: Hour 6:00 PM Day 30 Month 11 Year 1974

The above well was plugged as follows:

1430'--8 5/8" Surface casing, cement circulated.

Circulated hole with heavy mud. Pulled DP to 2975' and displaced 60 Sx. cement thru DP. Pulled DP to 900' and displaced 50 Sx. cement thru DP. Pulled DP to 550' and displaced 35 Sx. cement thru DP. Pulled DP, set bridge @ 45' with 1/2 sack hulls and 15 sacks cement to bottom of cellar. (By Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/13/74  
INV. NO. 464-w