

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dorchester Exploration, Incorporated,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Brinkman Well No. 1

Location CSW74 Sec. 29 Twp. 18 Rge. (E) (W) 40

County Greeley Total Depth 3000'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sterling Drilling Company.

Address Box #129, Sterling, Kansas. License No.       

Operation Completed: Hour 7:30 PM Day 27 Month 2 Year 1974

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement thru DP from 1250' to 925'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichel  
Well Plugging Supervisor

DATE 3/5/74

INV. NO. 8700-U