

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00807-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 7-2S-18W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: REECE C Well #: 7  
County: PHILLIPS Total Vertical Depth: 3485 feet

Operator License No.: 3182  
Op Name: NPF ENERGY CORPORATION  
Address: PO BOX 3827  
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	187	0	w/unknown sxs cmt
PROD	5.5	3484	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2011 8:30 AM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: PAT H COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered 365 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2011 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3290'. Tagged solid. Pulled one joint tubing to 3260'.  
Pumped 8 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1740' - pumped 90 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 870' - pumped 125 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.  
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 50 sxs 60/40 pozmix - 4% gel.  
No pressure.

Perfs:

Top	Bot	Thru	Comments
3460	3464		
3424	3429		
3406	3410		
3357	3363		

Remarks: COPELAND ACID & CEMENTING-TICKET #36340.

Plugged through: TBG

RECEIVED  
JUN 09 2011

KCC WICHITA

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

Form CP-2/3

JUN 02 2011