

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00802-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 7-2S-18W  
2870 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: REECE C Well #: 2  
County: PHILLIPS Total Vertical Depth: 3491 feet

Operator License No.: 3182  
Op Name: NPF ENERGY CORPORATION  
Address: PO BOX 3827  
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205	0	w/200 sxs cmt
PROD	5.5	3490	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2011 3:30 PM  
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION  
Proposal Rcvd. from: PAT COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed: Ordered 335 sxs 60/40 pozmix - 4% gel - 450# hulls.  
Plugging: Ran tubing in the hole. Tubing stacked out at 1860'.  
Method: Tried to wash over - could not wash over.  
Called the Hays Office and was told to go ahead and plug at 1860'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2011 7:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1845' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 930' - pumped 140 sxs 60/40 pozmix - 4% gel with 250# hulls to circulate to surface.  
Pulled all tubing Topped off 5 1/2" casing with 45 sxs 60/40 pozmix - 4% gel.  
Hooked to 8'5/8" x 5 1/2" annulus. Pumped 50 sxs 60/40 pozmix - 4% gel.  
No Pressure.

Perfs:

Top	Bot	Thru	Comments
3442	3456		

RECEIVED  
JUN 09 2011  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36341.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*  
(TECHNICIAN)

CM

Form CP-2/3

JUN 02 2011