

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00614-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 16-9S-16W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MEYERS Well #: 1
County: ROOKS Total Vertical Depth: 3590 feet

Operator License No.: 33778
Op Name: SHORELINE ENERGY PARTNERS, LLC
Address: 453 S WEBB RD # 100
WICHITA, KS 67207

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------------|
| SURF | 8.625 | 218 | 0 | 130 SX |
| PROD | 5.5 | 3500 | 0 | w/unknown sxs cmt |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2011 3:00 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: HI LEWIS Company: SHORELINE ENERGY PARTNERS, Phone: (314) 214-1738

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 750# hulls.
Perfed at 1900' - 1340' - 875' - 210'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2011 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' - pumped 175 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1900' - pumped 125 sxs 60/40 pozmix - 4% gel with 250# hulls.
Pulled tubing to 1000' - pumped 110 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 10 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3402 | 3407 | | |
| 3371 | 3375 | | |
| 3370 | 3374 | | |
| 3270 | 3275 | | |
| 3260 | 3266 | | |

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: TBG

RECEIVED
JUN 09 2011

KCC WICHITA

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

MAY 25 2011