

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-01393-00-01  
Spot: SWNESENV Sec/Twnshp/Rge: 36-12S-22W  
3440 feet from S Section Line, 3001 feet from E Section Line  
Lease Name: OGALLAH UNIT Well #: TR2-9  
County: TREGO Total Vertical Depth: 4290 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	223	0	200 SX
PROD 7		3982	0	175 SX

Well Type: SWD UIC Docket No: D19246.0 Date/Time to Plug: 05/13/2011 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls - 28 sxs gel. PC at 1746'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2011 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 125 sxs cement with 300# hulls - followed with 28 sxs gel - followed with 300 sxs cement and 400# hulls.  
Topped off with 45 sxs cement - full.  
Tied onto backside - pumped 5 sxs cement.  
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3982	4290		ARBUCKLE(OPEN)

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4907.

Plugged through: CSG

RECEIVED  
JUN 09 2011  
KCC WICHITA

District: 04

Signed *Marvin Mills*  
(TECHNICIAN) CM

Form CP-2/3

cc to WIC 7/06

MAY 26 2011