

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01371-00-00
Spot: NWNESW Sec/Twnshp/Rge: 26-12S-22W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SCHOENTHALER Well #: 9
County: TREGO Total Vertical Depth: 4035 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304	0	150 SX
PROD	5.5	4024	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2011 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 355 sxs 60/40 pozmix - 4% gel - 600# hulls - 14 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2011 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3499' - pumped 14 sxs gel - followed with 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1798' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 962' - pumped 90 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Closed 5 1/2" casing and pumped 70 sxs 60/40 pozmix - 4% gel - circulating out of 8 5/8" x 5 1/2" annulus.
S.I.P. 200#.
Pulled all tubing. Hooked to 5 1/2" casing - pumped 20 sxs 60/40 pozmix - 4% gel.
S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3988	4035		ARBUCKLE

RECEIVED
JUN 09 2011

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4837.

KCC WICHITA

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

MAY 25 2011