

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01389-00-00
Spot: SWNENW Sec/Twnshp/Rge: 36-12S-22W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SCOTT C Well #: 5
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	505	0	325 sx
PROD	5.5	4004	0	175 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2011 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls - 14 sxs gel.
Shoot perfs at 1790' - 970' - 400'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2011 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' - pumped 14 sxs gel - followed with 75 sxs cement with 200# hulls.
Pulled tubing to 1800' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 950' - pumped 100 sxs cement - good circulation.
Pulled tubing out - tied onto casing and squeezed with 25 sxs cement.
Max. P.S.I. 500#.
Tied onto backside - squeezed with 15 sxs cement.
S.I.P. 300#
Fill down 5 1/2" casing with 20 sxs cement to top off - full.

Perfs:

Top	Bot	Thru	Comments
4004	4030		

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4910.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
JUN 09 2011
KCC WICHITA

Form CP-2/3

MAY 26 2011