

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00849-00-01  
Spot: SESESE Sec/Twnshp/Rge: 26-12S-22W  
343 feet from S Section Line, 440 feet from E Section Line  
Lease Name: OGALLAH UNIT Well #: 6-4  
County: TREGO Total Vertical Depth: 4232 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

| String | Size  | Depth (ft) | Pulled (ft) | Comments          |
|--------|-------|------------|-------------|-------------------|
| SURF   | 10.75 | 316        | 0           | 225 SX            |
| PROD   | 7     | 3978       | 0           | w/unknown sxs cmt |

Well Type: EOR UIC Docket No: E19089.1 Date/Time to Plug: 05/16/2011 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 460 sxs 60/40 pozmix - 4% gel - 700# hulls - 28 sxs gel. DV at 1893'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2011 2:10 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 7" casing - pumped 125 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pumped 28 sxs gel spacer - followed with 300 sxs 60/40 pozmix - 4% gel with 400# hulls.  
Shut down - well was on a vacuum.  
Shut down to plug another well.  
Topped off 7" casing with 35 sxs 60/40 pozmix - 4% gel.  
Hooked 10 3/4" x 7" annulus.  
S.I.P. 200#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3978 | 4232 |      | ARBUCKLE |

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4836.

Plugged through: CSG

RECEIVED  
JUN 09 2011

KCC WICHITA

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

cc to UIC 7/66

MAY 25 2011