

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-21165-00-00
Spot: NWNE Sec/Twnshp/Rge: 27-29S-41W
660 feet from N Section Line, 1980 feet from E Section Line
Lease Name: TILLEY PAINTER Well #: 1
County: STANTON Total Vertical Depth: 5700 feet

Operator License No.: 34004
Op Name: SAXON OIL COMPANY
Address: 5910 N CENTRAL EXPY STE 1250
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1846		WITH 580 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/06/2010 6:45 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 05/06/2010 8:45 PM KCC Agent: STEVE DURRANT

Actual Plugging Report: _____ Perfs: _____

1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
JUN 09 2011
KCC WICHITA

District: 01 Signed Steve Durrant (TECHNICIAN)

RECEIVED
MAY 24 2011
KCC DODGE CITY