

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21088-00-00
Spot: SWSESE Sec/Twnshp/Rge: 8-28S-16W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: FANKHAUSER Well #: 1
County: KIOWA Total Vertical Depth: 5000 feet

Operator License No.: 31000
Op Name: PRATER OIL & GAS OPERATIONS, INC.
Address: 906 WILLIAM WAY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4675		WITH 2 SX CMT
SURF	8.625	427		WITH 325 SX CMT
PROD	5.5	4998	2200	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2011 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-0020

Proposed Plugging Method: CIBP @ 4675' WITH 2 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2011 3:15 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SET CIBP @ 4675' WITH 2 SX CMT. 1ST PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4808	4816		
4743	4746		
4726	4730		
4717	4719		

RECEIVED
JUN 15 2011

KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)
PART II

RECEIVED

JUN - 8 2011

KCC DODGE CITY

Form CH243