

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21006-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 2-14S-32W
746 feet from N Section Line, 916 feet from W Section Line
Lease Name: ROSE E Well #: 1
County: LOGAN Total Vertical Depth: 4634 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261	0	

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/10/2011 12:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: RICK Company: RAYMOND OIL COMPANY, INC. Phone: (316) 267-4214

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 06/10/2011 9:45 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfs:

1st. Plug at 2320' w/25 sxs.
2nd. Plug at 1175' w/100 sxs.
3rd. Plug at 310' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Remarks: CONSOLIDATED OIL WELL SERVICES.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED Form CP-2/3

JUN 17 2011

KCC WICHITA

JUN 15 2011