

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20163-00-00
Spot: SESWNESE Sec/Twnshp/Rge: 12-20S-36W
1420 feet from S Section Line, 737 feet from E Section Line
Lease Name: HOLSTEIN, ALFRED Well #: 1
County: WICHITA Total Vertical Depth: 5127 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	254		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/13/2011 9:30 AM
Plug Co. License No.: 34127 Plug Co. Name: TOMCAT DRILLING LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2215' WITH 50 SX CMT. 2ND PLUG AT 1240' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 280' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 06/13/2011 11:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report: _____ Perfs: _____

1ST PLUG AT 2215' WITH 50 SX CMT. 2ND PLUG AT 1240' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 280' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: **OPERATOR PLUGGED WELL WITHOUT CALL ING KCC FOR PLUGGING ORDERS.** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED CEMENTING.

Plugged through: DP

District: 01

RECEIVED
JUN 16 2011
KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED
JUN 17 2011
KCC WICHITA

Form CP-2/3