

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21983-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 32-17S-29W
2013 feet from S Section Line, 2038 feet from W Section Line
Lease Name: DAMEWOOD 32 Well #: 1
County: LANE Total Vertical Depth: 4547 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4260		WITH 3 SX CMT
SURF	8.625	253		WITH 160 SX CMT
DVT		2132		WITH 260 SX CMT
PROD	5.5	4528	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2011 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: HAROLD BELLERIVE, X-H Company: O'BRIEN RESOURCES Phone: (785) 635-4531

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS & 3 SX CMT. RUN TBG TO 2190' & 50 SX CMT. PLUG AT 1200' WITH 80 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2011 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4260' WITH 3 SX CMT. 1ST PLUG RUN TBG TO 2100' & PUMP 70 SX CMT. 2ND PLUG PULLED TBG TO 1200' & PUMP 80 SX CMT. 3RD PLUG PULLED TBG TO 270' & PUMPED 65 SX CMT. CMT CIRCULATED TO SURFACE. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4314	4317		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

RECEIVED
JUN 16 2011
KCC DODGE CITY

RECEIVED
JUN 17 2011
KCC WICHITA
Form CP-2/3