

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00801-00-00
Spot: NENENE Sec/Twnshp/Rge: 7-2S-18W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: REECE C Well #: 1
County: PHILLIPS Total Vertical Depth: 3431 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	158	0	w/unknown sxs cmt
PROD	5.5	3432	0	150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2011 12:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: PAT COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 4% gel - 500# hulls.
06/08/2011 - Ran sandline to 3100'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2011 2:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1854'. Hard bridge - unable to get thru.
Copeland Acid and Cementing pumped 260 sxs 60/40 pozmix - 4% gel.
PTOH. Squeezed 30 sxs 60/40 pozmix - 4% gel with 100# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside pumped 75 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3407	3415		
3393	3397		
3372	3378		

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

KCC WICHITA

JUN 13 2011