

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00826-00-00
Spot: SESENE Sec/Twnshp/Rge: 12-2S-19W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: MORGAN B Well #: 2
County: PHILLIPS Total Vertical Depth: 3512 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	275	0	200 SX
PROD	5.5	3511	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2011 8:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: PAT COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2011 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2474'. Hard bridge - unable to get below.
Copeland Acid and Cementing pumped 100 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1730'. Copeland Acid and Cementing pumped 165 sxs cement with 200# hulls.
PTOH. Pumped 80 sxs cement down 5 1/2" casing - opened backside and circulated cement.
Shut in backside and squeezed 15 sxs down 5 1/2" casing.
Max. P.S.I. 200#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3462	3473		
3448	3454		
3438	3443		
3401	3406		
3364	3371		
3349	3353		
3307	3310		
3297	3302		

Remarks: COPELAND ACID AND CEMENTING SERVICES.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
JUN 17 2011
KCC WICHITA

Form CP-2/3