

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20113-00-01  
Spot: NESE Sec/Twnshp/Rge: 8-1S-26W  
2120 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HUFF B Well #: 3  
County: DECATUR Total Vertical Depth: 3353 feet

Operator License No.: 4472  
Op Name: N.F. PRODUCERS, INC.  
Address: 1236 N. FAVER DR  
CASTLE ROCK, CO 80109

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7.625	223	0	125 SX
T1	2.375	3343		
MSCC		1986		
PROD	4.5	3453	0	375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2011 11:00 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: BRETT HILEDBRAND Company: N.F. PRODUCERS, INC. Phone: (303) 688-4552

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Fluid level at 700'.  
DV at 1986' w/200 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/08/2011 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3030'. Consolidated Oil Well Service pumped 100 sxs 60/40pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1500'. Consolidated Oil Well Service pumped 110 sxs cement with 100# hulls - circulated cement.  
PTOH. Topped 4 1/2" casing off with 10 sxs cement - casing full.  
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3348	3350		
3316	3318		
3275	3279		
3239	3241		

Remarks: CONSOLIDATED OIL & CEMENTING.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

RECEIVED

JUN 17 2011

Form CP-2/3

JUN 13 2011

KCC WICHITA