

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23713-00-00
Spot: NESENE SW Sec/Twnshp/Rge: 20-15S-15W
1760 feet from S Section Line, 2390 feet from W Section Line
Lease Name: MAIER TRUST ET AL Well #: 1-20
County: RUSSELL Total Vertical Depth: 3420 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.38	881		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/22/2011 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4573

Proposed Plugging Method: Ordered 180 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 05/22/2011 2:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st. Plug at 3300' w/25 sxs.
2nd. Plug at 930' w/40 sxs.
3rd. Plug at 325' w/60 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

JUN 17 2011

JUN 06 2011

KCC WICHITA