

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23725-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 30-9S-21W
1538 feet from S Section Line, 1114 feet from E Section Line
Lease Name: MCKENNA Well #: 2
County: GRAHAM Total Vertical Depth: 3971 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/05/2011 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: PIONEER RESOURCES Phone: (785) 543-5556

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 04/05/2011 10:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 3864' w/25 sxs.
2nd. Plug at 1836' w/25 sxs.
3rd. Plug at 1052' w/100 sxs.
4th. Plug at 271' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

KCC WICHITA

JUN 06 2011