

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-00037-00-01 }
Spot: SWNW Sec/Twnshp/Rge: 33-8S-36W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: STUDER B Well #: 1
County: THOMAS Total Vertical Depth: 5300 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4520		
SURF	8.625	326	0	300 SX
PROD	4.5	4775	0	250 SX 60-40 POZ

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2011 12:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: PAUL Company: THOROUGHbred ASSOCIATES L. Phone: (316) 685-1512

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 300# hulls.
Shoot perfs at 2880' - 1850' - 315'.
CIBP at 4520'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2011 5:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4300' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2900' - pumped 100 sxs cement with 100# hulls.
Pulled to 1505' - pumped 230 sxs cement - good circulation out the casing and the backside.
Pulled tubing out - topped off casing with 20 sxs cement - full.

Perfs:


Top	Bot	Thru	Comments
4697	4700		
4374	4402		

Remarks: CONSOLIDATED CEMENTING COMPANY-TICKET #28033.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

JUN 08 2011

KCC WICHITA