

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-01994-00-00  
Spot: NESESENE Sec/Twnshp/Rge: 14-21S-20E  
3159 feet from S Section Line, 215 feet from E Section Line  
Lease Name: WEST VAN WINKLE Well #: T-30X  
County: ANDERSON Total Vertical Depth: 660 feet

Operator License No.: 34170  
Op Name: SIRIUS ENERGY CORP.  
Address: 526 COUNTRY PL, SOUTH  
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	12	20		NA
PROD 2		630		NA

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2011 12:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: RANDY TETER Company: \_\_\_\_\_ Phone: (785) 448-8571

Proposed Plugging Method: RUN 3/4 INCH PIPE APPROX. 660 FEET AND FILL 2 INCH PIPE WITH APPROX. 20 SACKS. RUN 1 INCH PIPE TO BOTTOM AND FILL BACKSIDE TO SURFACE WITH APPROX. 100 SACKS.

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/05/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 630 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO BOTTOM AND PUMP 102 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 110 SACKS OF CEMENT.

Perfs:

RECEIVED  
JUN 30 2011 LS  
KCC Chanute District

Remarks:

Plugged through: TBG

RECEIVED  
JUL 08 2011  
KCC WICHITA

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)