

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-02026-00-00

Spot: NWSWNWSW

Sec/Twnshp/Rge: 13-21S-20E

1902 feet from S Section Line, 5182 feet from E Section Line

Lease Name: WEST VAN WINKLE

Well #: L-28X

County: ANDERSON

Total Vertical Depth: 660 feet

Operator License No.: 34170

Op Name: SIRIUS ENERGY CORP.

Address: 526 COUNTRY PL. SOUTH
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	12	20	0	
------	----	----	---	--

PROD	2	630		
------	---	-----	--	--

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/17/2011 12:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: RANDY TETER

Company:

Phone: (785) 448-8571

Proposed Run 3/4 inch pipe approx. 660 feet and fill 2 inch pipe with approx. 20 sacks.
Plugging Run 1 inch pipe to bottom and fill backside to surface with approx. 100 sacks.
Method:

Plugging Proposal Received By: LEVI SHORT

WitnessType: NONE

Date/Time Plugging Completed: 05/17/2011 12:00 AM

KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 630 FEET AND FILL WITH 8 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO BOTTOM AND PUMP 112 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT.

RECEIVED

JUL 6 2011

KCC Chanute Dist. #3

LS


Remarks:

Plugged through: TBG

RECEIVED
JUL 08 2011

District: 03

Signed



(TECHNICIAN)

KCC WICHITA