

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20722-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 7-29S-23W
1230 feet from S Section Line, 1760 feet from W Section Line
Lease Name: SCHLICHTING Well #: 1-7
County: FORD Total Vertical Depth: 5430 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5170		WITH 2 SX CMT
SURF	8.625	634		WITH 400 SX CMT
PROD	4.5	5423	2480	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2011 11:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: M.L. KORPHAGE Company: VINCENT OIL Phone: (316) 377-3373

Proposed Plugging Method: SET CIBP @ 5170' WITH 2 SX CMT OR SAND TO 5170' WITH 4 SX CMT. PLUG AT 1480' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 320' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/29/2011 12:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5170' WITH 2 SX CMT. 1ST PLUG AT 1480' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 320' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT DID NOT CIRCULATE. 5/25/11: FOUND TOC @ 150'. 6/7/11: DUMPED 2.75 YARDS OF CMT DOWN THE 8 5/8" CASING WITHOUT FILLING UP. TOC WAS INCORRECT. 6/29/11: RAN TBG TO TAG CMT AT 660'. PULLED TBG TO 610'. PUMPED 220 SX CMT WITH NO RETURNS. WHILE PULLING TBG, IT WAS FOUND THAT CMT HAD COME TO APPROXIMATELY 90' FROM SURFACE. LAID TBG DOWN & PUMPED 30 SX CMT DOWN 8 5/8". SURFACE PIPE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5219	5232		Congl chert

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES ON PLUG ON 5/23/11 & ALLIED ON 6/29/11. JUL 08 2011
Plugged through: TBG

KCC WICHITA

District: 01

Signed Eric Maclaren
(TECHNICIAN)

RECEIVED
JUN 30 2011
KCC DODGE CITY

Form CD-273